

# **Accordion VL Sound Divider Series**

#### Introduction:

The following three (3) part specification offers the Standard and *Optional* features for the Model VL-2, VL-6, VL-8 Accordion Partitions.

In order to assist you with the design criteria KWIK-WALL has provided a Product Guide for the Model VL-2, VL-6, VL-8.

The Product Guide indicates the acoustical ratings (STC) available, and also establishes the maximum partition height, width and weight.

MODEL VL PRODUCT GUIDE					
MODEL	STC RATING	STACK WIDTH PROFILE	MAXIMUM PARTITION HEIGHT	MAXIMUM WALL WIDTH*	MAXIMUM HANGING WEIGTH Ib./ft.²
VL-2	35	9 1/2" [241]	16'-0" (4.88 m)	25'-0" (7.62 m)	2.65 (12.9 kg/m²)
VL-6	38	9 1/2" [241]	16'-0" (4.88 m)	25'-0" (7.62 m)	3.15 (15.4 kg/m²)
VL-8	40	10" [254]	16'-0" (4.88 m)	25'-0" (7.62 m)	3.65 (17.8 kg/m²)

<sup>\*</sup>Note: Maximum partition span for Single Partitions is 25'-0" (7.62 m) or 50'-0" (15.24m) for Bi-Parting partitions.

# **Model VL Accordion Product Specification**

### **PART 1 GENERAL**

## 1.1 Scope

- 1.1.1 Furnish and install accordion partition and suspension system specified.
- 1.1.2 Provide all tools, equipment and labor necessary to complete the accordion partition installation.

### 1.2 Related Work By Others

- 1.2.1 Preparation of opening and surrounding construction.
- 1.2.2 All header, support structure, partition pockets, backing at jambs and wall surface preparation.
- 1.2.3 All adjacent structure sound attenuation work, insulation and fireproofing as required in section 1.4.

#### 1.3 Submittals

- 1.3.1 Complete shop drawings, indicating location and product construction details. Include plans, elevations, sections, and attachment to other construction.
- 1.3.2 Partition covering samples showing full range of colors available.
- 1.3.3 Manufacturer's literature, including product brochures, technical sheets, installation instructions and operation and maintenance instructions as requested.

# 1.4 Quality Assurance

- 1.4.1 Accordion partition acoustical rating shall be verified through testing by qualified independent acoustical testing laboratory in accordance with ASTM E90 and ASTM E413 test procedures.
- 1.4.2 Surface burning rating shall be class A in accordance with ASTM E84.
- 1.4.3 Preparation of the opening shall conform to the criteria set forth per ASTM E557.

# 1.5 Delivery and Storage

- 1.5.1 Product shall be packaged for shipment from manufacturer in custom-fabricated protective wrapping.
- 1.5.2 All shipping containers shall be properly marked externally for content and destination.
- 1.5.3 Contractor shall assume responsibility for delivered product integrity if product is shipped and stored prior to installation. Contractor is responsible for product integrity after wall delivery.
- 1.5.4 Contractor shall insure the area to be used for uncrating and/or staging the accordion partition prior to installation is clean and free of debris.

### 1.6 Warranty

- 1.6.1 KWIK-WALL's limited warranty guarantees the product to be free from factory originated defects in materials and workmanship for a period of five (5) years from the date of installation.
- 1.6.2 Pantographic frame, wheels, trolleys and track shall be guaranteed against operating failure in the course of normal usage for a period of five (5) years from the date of installation.

#### **PART 2 PRODUCTS**

# 2.1 Acceptable Manufacturers

- 2.1.1 Accordion partitions shall be Model (*select*): VL-8, VL-6 or VL-2 supplied by Curition a division of Kwik-Wall..
- 2.1.2 Other manufacturers wishing to bid product similar to KWIK-WALL's VL Series shall submit data to the architect at least ten (10) days prior to bid opening to support compliance with bid specification.
- 2.1.3 Alternative bidders shall guarantee their product specifications comply with the product specified.

# 2.2 Operation

2.2.1 Accordion partitions shall be top supported and moved manually to the closed (latched) position or to the open (stacked) position by pulling or pushing the handle through the range of partition movement. The partition shall be secured in the closed position by the latch mechanism, tiebacks or pocket door, if specified, in the closed position.

#### 2.3 Materials

- 2.3.1 Partition covers shall be fastened to the frame with permanent rivets through concealed nylon webbing, double stitched to the inside surface. Rivets shall not penetrate outer lining and shall not be visible.
- 2.3.2 Sound retardant liners shall be filled polyvinyl sheets. VL-8 to have 1/2" [13mm] fiberglass blankets.
- 2.3.3 Covers shall have multi-ply rubberized sweep strips of neutral color, top and bottom, both sides, for sound attenuation. Top sweep strips shall be 1/2" [13mm]. Bottom sweep strips shall be (select): (A) 1 1/2" [38mm] (standard)
  - (B) 4" [102mm] for field trimming to compensate for non-level floor conditions.
- 2.3.4 Internal framing shall be 3/16" [5mm]-diameter wire rod, welded to interlocking, collapsible/extendible full channel hinges and shall provide true pantographic motion. Hinges shall be custom formed 14-gauge [2mm] steel plate, welded to frame at top, bottom and intermediate points not to exceed 3'-6" [1067mm] vertical spacing on any partition over 6'-8" [2032mm] in height. Steel spacing chain shall be installed along the frame centerline to control hinge movement.
- 2.3.5 Lead and end posts shall be of minimum 14-gauge [2mm] box-channel steel. The lead post shall be mounted to the leading partition edge and will contain die cast chrome plated latch hardware and rubber acoustical seals. All jambs and posts and shall be wrapped with the same material as the partition covers.

#### 2.3.6 Stack dimensions shall be:

 VL-8
 VL-6
 VL-2

 Stack Depth (in./ft. of door)
 2.6" [66]
 2.0" [51]
 2.0" [51]

 Stack Width
 10" [254]
 9.5" [241]
 9.5" [241]

### 2.3.7 Hanging weight shall be:

VL-8 VL-6 VL-2

lbs./sq. ft.

(kg/sq. m.) 7.0 (34.2) 3.7 (18.1) 3.2 (15.6) 2.7 (13.2)

### 2.4 Finishes

- 2.4.1 Panel face finish shall be factory-applied Class "A" rated material (select):
  - (A) Reinforced vinyl fabric with woven backing weighing not less than 21 ounces per yard [653 g/m].
  - (B) Carpet of non-woven, 100% Polyester staple fiber with fusible latex backing weighing not less than 23 ounces per yard [715 g/m].
  - (C) Optional Upgrade Fabric: consisting of fade and tear resistant fabric that resists water-based stains weighing 13 oz./lin. yd. (403 g/lin. m).
  - (C) Customer supplied material. (subject to factory approval)

# 2.5 Options

- 2.5.1 Available options shall include:
  - (A) Locks: one or both sides.
  - (B) Radius construction for curved applications.
  - (C) Track switches for alternate storage or multi-location applications.
  - (D) Floating posts for latching of multiple partitions in L, T and X configurations.
  - (E) Sliding jamb boards for pocket storage.
  - (F) Conversion latch.

# 2.6 Suspension System

- 2.6.1 Track shall be Kwik-Wall #4 architectural grade aluminum extrusion with custom taper design to prevent wheel chatter. Optional aluminum ceiling guard shall be available. Track mounting shall be (select): Surface Mounted or Concealed.
- 2.6.2 Frame shall be supported by 1" [25mm] steel wheels mounted over matched precision bearings, with nylon tires affixed to load rated, heat treated swivel joint carriers.
- 2.6.3 Carriers shall be four-wheel units at the lead post and two-wheel units at every support point, with spacing of carriers not to exceed 11" [279mm] apart.

### 2.7 ACOUSTICAL PERFORMANCE

- 2.7.1 An accredited acoustical testing laboratory (U.S. Commerce, NVLAP) shall have tested laboratory acoustical performance of the partition in accordance with ASTM E90 test standards. Laboratory Sound Transmission Classification (STC) ratings shall be: VL-8 VL-6 VL-2 STC 40 38 35
- 2.7.2 Copies of original test reports shall be made available upon request.

#### **PART 3 EXECUTION**

#### 3.1 Preparation

- 3.1.1 Preparation of opening to house accordion partition shall be by others in accordance with architectural plans, manufacturers shop drawings and ASTM E557.
- 3.1.2 Prior to installation, a manufacturer-authorized representative shall inspect the accordion partition. Any discrepancies noted shall be brought to the attention of the site supervisor, architect and manufacturer for remediation.

### 3.2 Installation

- 3.2.1 Installation shall be accomplished in strict accordance with approved shop drawings and architectural plans.
- 3.2.2 Installation shall be accomplished by an authorized representatives in full compliance with manufacturer's written instructions (included with each shipment).
- 3.2.3 General Contractor shall be responsible for on-site product integrity.
- 3.2.4 Installer shall train owner's representatives in proper wall operation and maintenance.
- 3.2.5 Installer shall insure removal and proper disposal of all shipping materials and packaging associated with the accordion partitions from the work site upon completion of the installation.

#### For additional information contact:

Kwik-Wall 4650 Industrial Ave. Springfield, IL 62703

Phone: 217-522-553 Fax: 217-522-1170

Website: www.kwik-wall.com Email: waudb@kwik-wall.com

Note:

Due to ongoing research and development, some variations may occur in product specifications.

12-16